

To: 1051569
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,739-0000 ¹⁹⁸
NW SE, SEC. 4, T. 35 S, R. 21 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9154

1980 feet from S section line

1980 feet from E section line

Operator: Crescent Drilling & Development, Inc.
Name & Address: P.O. Box 4495
Houston, TX 77210-4495

Lease Name Tuttle Well # 1-4

County Clark 250.73

Well Total Depth 7715 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1526

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 3 Month: 8 Year: 19 92

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 7715' w/380 sx cement, PBDT 5790', Perfs at 5609-20, 5637-64, 5694-5704, 5708-18

1st plug pump 2 sx hulls and 20 sx cement on bottom,

2nd plug pump 50 sx cement at 1580', fill with mud,

3rd plug pump 10' sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10 a.m. Day: 4 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 5500',

2nd plug pumped 40 sx cement at 1550',

3rd plug pumped 20 sx cement at 500',

4th plug pumped 10 sx cement at 40'.

Heavy mud between plugs.

Remarks: Used common cement by Sargent's. Recovered 4032' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form)

I (did / ~~did not~~) observe this plugging.

9-11-92
36088

Signed Richard W. Lacy (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1992
CONSERVATION DIVISION
Wichita, Kansas