

1 51716

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-21,098 - 0000
App. SW SE NE, SEC. 2, T 35 S, R 21 W 1/4
2800 feet from S section line
1160 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31093
Operator: Becker Oil Corporation
Name & Address: 212 First National Bldg.
Ponca City, OK 74601

Lease Name Snake Creek Ranch Well # 1
County Clark 184.76
Well Total Depth 5685 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 660

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Gabbert/Jones, Inc. License Number 5842
Address English Key Bldg., 333 E. English, Ste. 215, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 30 Month: 8 Year: 19 93

Plugging proposal received from Walt Prather
(company name) Gabbert/Jones, Inc. (phone) 316-263-6209

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 950' with 50 sx cement, 2nd plug at 690' with 50 sx cement,
3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 5:30 p.m. Day: 30 Month: 8 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement,
2nd plug at 690' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 15 1993
9-15-93
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

38685

Signed Richard W. Lacey (TECHNICIAN)

EFFECTIVE DATE: 8-22-93

State of Kansas 15-025-21,098-0000

FORM MUST BE TYPED

DISTRICT # 1
SEAS Yes No

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 8 18 93
month day year
Spot 2 1/2 Sec 2 Twp 35 S. Rg 21 East West

OPERATOR: License # 31093
Name: Becker Oil Corporation
Address: 212 First National Bldg.
City/State/Zip: Ponca City, OK 74601
Contact Person: Clyde M. Becker
Phone: (405) 765-8788

2800 feet from South North line of Section
1160 feet from East West line of Section
IS SECTION REGULAR X IRREGULAR?

CONTRACTOR: License #: Unknown
Name: Gabe White Jones

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Clark
Lease Name: Snake Creek Ranch Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
Oil ... Enh Rec ... Infield ... Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
OUWD ... Disposal ... Wildcat ... Cable
Seismic; ... # of Holes ... Other
Other
If OUWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Morrow
Nearest lease or unit boundary: 1160'
Ground Surface Elevation: 3840' est. feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 105'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: (700) 200
Length of Conductor pipe required: None
Projected Total Depth: 5700
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond ... other

Directional, Deviated or Horizontal wellbore? ... yes ... no
If yes, true vertical depth:
Bottom Hole Location:

DNR Permit #:
Will Cores Be Taken? ... yes ... no
If yes, proposed zone:
200' Alt. I Req.

AFFIDAVIT

Exp. 2/18/94
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

098
Pusher Clyde Becker Walt Prather
SPUD DATE 8-20-93 INIT. Jan
LENGTH SURFACE PLANNED 620
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 660 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 5685 FORMATION
RAN PIPE @ SX DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 950 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 690 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
Hauling
TECHNICIAN R.L DATE 8-30-93
TYPE OF CEMENT 60/40 p02 696gt
STARTING TIME : (AM/PM) DATE
COMPLETION TIME 5:30 (AM/PM) DATE 9-20-93
CEMENT COMPANY Hall