

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finley State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-216730000

LEASE NAME WILSON "F"

WELL NUMBER 1

2000 Ft. from S Section Line

1750 Ft. from E Section Line

SEC. 13 TWP. 34 RGE 34 (E) or (W)

COUNTY SEWARD

Date Well Completed 2-25-98

Plugging Commenced 10-26-98

Plugging Completed 10-27-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1626	NONE
				5-1/2"	6695	2504'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
MIRU PU. PMP 3 SKS HULLS & 25 SKS 60/40 POZ CMT W/6% GEL TO PLUG PERES AT 6140-6146'. PULL FREE POINT. CUT OFF 5-1/2" CASING AT 4011'. COULD NOT PULL. CUT OFF 5-1/2" CASING AT 3218'. COULD NOT PULL. CUT OFF 5-1/2" CASING AT 2504'. PULL 5-1/2" CSG TO 2424' & SPOT 30 SKS CMT. PULL 5-1/2" CSG TO 1675' & SPOT 50 SKS CMT AT 1675' TO 1575'. TOH TO 600' & SPOT 40SKS AT 600' TO 100'. TOH TO 43' & SPOT 10SKS CMT FROM 43' TO 3'. 9PPG MUD BETWEEN PLUGS. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.) 11-4-98

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1998

Frederic L. Henry
 Notary Public

My Commission Expires 5-15-99