

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-10150 - 0000

LEASE NAME McGILL

WELL NUMBER 1-10

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 10 TWP. 34S RGE 34 (E) or (4)

COUNTY SEWARD

Date Well Completed 5-1960

Plugging Commenced 12-15-97

Plugging Completed 12-18-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-4-97 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation L. CHESTER Depth to Top 6345 Bottom 6405 T.D. 6453

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L. CHESTER	GAS	6345	6405	8-5/8	1684	4'
				4-1/2	6449	2706

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 MIRU PL. RIG DWN WH. 1D 3-3/8 TBG. 1D 2-3/8 TBG. PMP 2 SXS HULLS & 20 SXS CMT TO PLUG PERES 6345-6145. SHOT OFF 4-1/2 CSG @ 2706. PMP 25 SXS CMT TO PLUG 2700 TO 2600. POH TO 1720. PMP 50 SXS CMT TO PLUG 1720 TO 1570. POH TO 650. PMP 40SXS CMT TO PLUG 650 TO 550. POH TO 40. PMP 40 SXS CMT TO PLUG 40' TO SURE. CUT OFF AND CAP 8-5/8 CSG 4' BELOW GL. RDMO. NOTIFY KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Shawn D. Young*
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

STATE CORPORATION COMMISSION (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1998

1-28-99

Shirley J Childers
 Notary Public

My Commission Expires:

