

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

20623 00 01  
API NUMBER 15-175-20673-A

LEASE NAME Seaton

WELL NUMBER 2

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 7 TWP. 34S RGE. 34W (E) or (W)

COUNTY Seward

Date Well Completed 10-11-89

Plugging Commenced 4-29-97

Plugging Completed 5-1-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rosel Energy Inc.

ADDRESS 302 S. Clay Liberal, Kansas

PHONE# 3886 624-4994 OPERATORS LICENSE NO. 5941

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Council Grove Depth to Top 3008 Bottom 3137 T.D. 3229

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1714	0
				4 1/2	3229	2028

1997  
KANSAS  
RECEIVED  
SCHEDULED  
CO

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Rosel perforators set CIBP W/2 sks. of cement on top Rosel ran CIBP to 2300 W 2'  
Pump 50 sks. of cement from 1750 to 1585 Pump 40 sks. of cement from 600' to 470'  
Cap well with 10 sks. of cement from 40 to 0  
Cut off 8 5/8 2' below ground level weld on Steel ID plate  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-05-6

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Keith Hill

(Address) Crown Consulting, Inc.  
P. O. Box 1816, Liberal, KS

SUBSCRIBED AND SWORN TO before me this 29th day of May, 19 97

Hele M. Smith  
Notary Public

My Commission Expires: \_\_\_\_\_





# CEMENT BOND LOG

15-175-20623-0001

RECEIVED  
KANSAS CORP COMM  
1997 APR 14 P 12:29

COMPANY ROSEL ENERGY, INC.

WELL SEATON #2

FIELD \_\_\_\_\_

COUNTY SEWARD COUNTY, KANSAS

LOCATION \_\_\_\_\_

SEC. 7 TWP. 34 S RGE. 34 W

OTHER SERVICES:

DERRICK TRAILER #101

PERMANENT DATUM: GROUND LEVEL ELEV. 2948

ELEV. K.B. 2960

LOG MEASURED FROM KELLY BUSHING 12 FT. ABOVE PERM. DATUM

D.F. 2959

DRILLING MEASURED FROM KELLY BUSHING

G.L. 2948

DATE	TIME	9-23-89	2100	TYPE DRILL FLUID	LOGGED WITH WATER IN HOLE.
RUN NO.	ONE			FLUID LEVEL	FULL
DEPTH DRILLER	3203			MAX. REC. TEMP.	
DEPTH LOGGER	3193			EST. CEMENT TOP	2156
BTM. LOG INTERVAL	3186			EQUIP.	LOCATION
TOP LOG INTERVAL	2000			UNIT #676	LIBERAL, KS.
OPEN HOLE SIZE	7 7/8			RECORDED BY	TOLLEFSON
DATE & TIME CEMENT				WITNESSED BY	MR. REYNOLDS
TYPE CEMENT OPER.	PRIMARY			SQUEEZE DEPTH	
FLOAT COLLAR/DV TOOL				SALINITY PPM CL	
AMOUNT & TYPE CEMENT				WEIGHT LB/GAL	VIS
AMOUNT & TYPE ADMIX				CALC. CEMENT TOP	2200
TRUCK NUMBER				SPACING RECORDED	3' SIGNAL & 5' VOL
				TOOL NUMBER	CB-2, PS-005

FOLD HERE