

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21495 - 0000

LEASE NAME EUBANK "B"

WELL NUMBER 8

1980 Ft. from S Section Line

3380 Ft. from E Section Line

SEC. 13 TWP. 34 RGE. 33 ( X ) or ( W )

COUNTY SEWARD

Date Well Completed 10-24-95

Plugging Commenced 11-12-95

Plugging Completed 11-12-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-11-95 (date)

by MR. RICHARD LACY (KCC District Agent's Name)

Is AC0-1 filed? YES (ATTACHED) If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1575	NONE
				5-1/2	2912	2000'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
MIRU PLUGGERS. PMPD 3 SX HULLS & 25 SX CMT PLUG FROM 2638-2438' PULLED FREE POINT ON 5-1/2 CSG @ 2000'. SHOT OFF 5-1/2 @ 2000' & PULLED TO 1625. PMPD 50 SX CMT PLUG FROM 1625-1475' PULLED 5-1/2 TO 550' & PMPD 50 SX CMT PLUG FROM 550-400' TOH & SPOTTED 10 SX CMT PLUG FROM 40-3' CUT OFF 8-5/8 CSG 3' BELOW GL & CAPPED. PERMANENTLY INSCRIBED WELL NAME AND LOCATION ON CAP. WITNESS: KCC REPRESENTATIVE MR. RICHARD LACY.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss. *Due 12-6-95*

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 17<sup>th</sup> day of November 1995

L. MARC HARVEY  
Notary Public - State of Kansas  
My Commission Expires 6-12-99  
Notary Public

My Commission Expires: \_\_\_\_\_