

15-175-10154-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME CONDIT UNIT

WELL NUMBER 1-1

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 12 TWP. 34SRGE. 33 (R) or (W)

COUNTY Seward

Date Well Completed 5/21/64

Plugging Commenced 2/29/88

Plugging Completed 3/4/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Water injector

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/17/87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Drillers log Filed w/Form CP-1

Producing Formation L. Chester Depth to Top 6255 Bottom 6269 T.D. 6384

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>L. Chester</u>	<u>Oil</u>	<u>Surf</u>	<u>1599</u>	<u>8-5/8</u>	<u>1599</u>	<u>0</u>
		<u>Surf</u>	<u>6380</u>	<u>5-1/2</u>	<u>6380</u>	<u>2227</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Rigged up Sargents. Spotted 25 sxs cmt, 1 sx hulls 6269-6100. Cut off casing at 2227.
Pmpd 30 sxs cmt 2220-2100, pmpd 50 sxs cmt 1640-1540, pmpd 25 sxs cmt 700-600, pmpd 10 sxs cmt 40-0. Cut off and capped 8-5/8 csq 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.


M. L Pease, Division Production Manager (Employee of Operator) or ~~XXXXXX~~ of above-described well, **RECEIVED** first duly sworn on oath, says: That I have knowledge of the facts, statements, and **STATE CORPORATION COMMISSION** contained and the log of the above-described well as filed that the same are true and correct, **COMMISSION** me God.

(Signature) M. L Pease

(Address) P. O. Box 351, Liberal, KS 67905

MAY 19 1988

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 88



Beverly J. Williams
Notary Public

November 21, 1990

DRILLER'S LOG

WELL NAME Worthington "A" #1 COMPANY OPERATING Anadarko Production Company
 ADDRESS of COMPANY Box 351, Liberal, Kansas

WELL LOCATION C 1/2 NE 1/4 SW 1/4,
1980 ft. North of South line,
1980 ft. East of West line; Sec. 12 Twp. 34 Rge. 33, Seward County, Kan

DRILLING STARTED 4-13, 1964 DRILLING COMPLETED 4-30, 1964
 WELL COMPLETED 5-21, 1964 WELL CONNECTED _____, 1964

ELEVATION 2830.44 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Chester	6255	6269	28	1000	7 1/2% NE Acid
				10000	gelled diesel

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	1599	650	None
5 1/2	6300	310	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand	0000	675			
Red Bed	675	1030			
Red Bed & Anhydrite	1030	1651			
Red Bed & Sand	1651	2366			
Anhydrite, Lime & Shale	2366	2557			
Lime & Shale	2557	5992			
Lime	5992	6179			
Lime & Shale	6179	6384			
Total Depth	6384				

RESULTS of INITIAL PRODUCTION TEST: WHOF 11,600 MCF/D