

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175 - 20,953-000

LEASE NAME Hatcher A

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4030 Ft. from S Section Line

3950 Ft. from E Section Line

SEC. 12 TWP. 34 RGE. 33 (X) or (W)

COUNTY Seward

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351 Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed _____

Character of Well P & A

Plugging Commenced 7-18-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-20-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Hugoton Depth to Top 2629 Bottom 2668 T.D. 2800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From 698	To Surf.	Size 8 5/8	Put in 698	Pulled out 0
		2799	Surf.	5 1/2	2799	792

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugs pumped down csq; 1 sx cottonseed hulks & 20 sxs cmt 2668' - 2540', pmp 30 sxs cmt 1300' - 1020' cut off 5 1/2" csq @ 792', pmp 50 sxs cmt 760' - 610', push wooden wiper plug to 40' w/10 sxs cmt 40' - 5'. Cut off surface csq 5' below surface and capped well. Cmt type; 60/40 POZ w/6% gel. Heavy drilling mud spotted between plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547


Address 620 S. Lincoln. Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67901



SUBSCRIBED AND SWORN TO before me this 21st day of September, 19 87
Beverly J. Williams
Notary Public

SEP 4 1987
9-4-87
CORPORATE DIVISION
Wichita, Kansas