

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,027 -00-00

LEASE NAME Covey

WELL NUMBER 1

2970 Ft. from S Section LI

1650 Ft. from E Section LI

SEC. 22 TWP. 27 RGE. 15 ~~XX~~ ^W

COUNTY Pratt

Date Well Completed 12-1-81

Plugging Commenced 10-14-92

Plugging Completed 11:45 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 10-14-92 (date)

by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top 4240 Bottom 4245 T.O. 4540

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	380	0
				4 1/2	4532	2611

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from ___ feet to ___ feet each
Bottom plug: Sanded to 4190 & bailed 4 sx cement.

Top plug: pumped 300 lb Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lbs Hulls, 8 5/8 Wiper plug, & 100 sx 60/40 with 6% Gel. Maximum pressure of 275 lbs, & shut in of 125 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.


(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1992

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 16 day of October, 19 92



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96