

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,484-00-00

LEASE NAME Country Estates

WELL NUMBER 1

SPOT LOCATION C NW NE

SEC. 35 TWP. 28 RGE. 12 (X) or (W)

COUNTY Pratt

Date Well Completed 10-5-84

Plugging Commenced 10-5-84

Plugging Completed 10-5-84

LEASE OPERATOR Vincent Oil Corporation
ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4612

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Well was plugged with 120 sxs 60/40 poz, 2% gel, 3% cc as follows: 840'-50 sxs; 450'-40 sxs; 40'-10 sxs with plug; rathole-10 sxs; mousehole-10 sxs.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149
Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little, Vice-President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little
(Address) P. O. Box 329, Pratt, Ks. 67124

OCT 15 1984
10-15-84
Pratt, Kansas



SUBSCRIBED AND SWORN TO before me this 10 day of October, 1984

Mary L. Tjaden
Notary Public

My Commission expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc.

DRILLER'S WELL LOG

Country Estates #1
 C NW NE Sec. 35-28S-12W
 Pratt County, Kansas
 Commenced: 9-25-84
 Completed: 10-5-84
 API #15-151-21,484
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	675	Sand	Ran 10 joints (422.50'), new 24#, 8rd, 8 5/8" surface casing. Set at 434' with 175 sxs Lite, 3%cc, 100 sxs Common, 2% Gel, 3% cc. Job by Buie, Ticket #3124. Cement did circulate. Plug down at 8:45 a.m. on September 26, 1984.
675	1880	Red Bed	
1880	2705	Shale	
2705	4449	Lime, Shale	
4449	4526	Simpson	
4526	4531	Lime, Shale	
4531	4607	Sand, Shale	RTD 4612'
4607	4612	Lime, Shale, T.D.	

Well was plugged with 120 sxs 60/40 poz, 2% gel, 3% cc as follows: 840'-50 sxs; 450'-40 sxs; 40'-10 sxs with plug; rathole-10 sxs; mousehole-10 sxs. Job by Buie, Ticket #1961. Complete at 9:15 p.m. on October 5, 1984. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88

OCT 15 1984
 WHEATSTATE OILFIELD SERVICES, INC.
 DODGE CITY, KANSAS