

15-119-10276-0000
J

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 40-15
LOCATION C SE NE
SEC. 12 TWP. 34S RGE. 30

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-12 Lease Hull
Operator Panhandle Eastern Pipe Line Address Liberal, Kansas
Field _____ County Meade
Total Depth 6220 Feet.

(Describe briefly the manner in which the well was plugged)

Rotary Mud from	6220	to	6016
Cement plug "	6016	"	5884
Rotary Mud "	5884	"	5400
Cement Plug "	5400	"	5333
Rotary Mud "	5333	"	2948
Cement Plug "	2948	"	2936
Rotary Mud "	2936	"	600
Cement Plug "	600	"	575
Roatry Mud "	575	"	23
Cement Plug "	15	"	8

The 13 3/8" OD surface casing is cut off 8' below the ground level and the cellar is filled with dirt.

AUG 30 1952
3-30-52
CONSERVATION DIVISION
Wichita, Kansas

P. J. Phillippe
District Conservation Agent

Date 8-23-52

PLUGGING
FILE SEC 12 TWP 34S RGE 30
BOOK 40 PAGE 15