

*49*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
NOV 13 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name William Gruenerwald & Assocs.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name Fox Well No. 2

Location NW NW Sec. 6 Twp. 34 Rge. 30 (X) (W)

County Meade Total Depth 6000'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 10 Month 11 Year 1967

The Above well was plugged as follows:

8 5/8" to 1436' circulated w/ cement      5 1/2" to 5998' cemented

Top perforations 5627'      Plug bottom w/ 25 sacks cement.

Top of cement 5500'      Mud 5500' to 650'

Spotted 35 sacks cement 650' to 550'      Mud 550' to 40'

Plug, Halls & 10 sacks cement 40' to 0'      Company Pump

Pulled 2620' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edmund J. Lued*  
Well Plugging Supervisor

11/13/67  
6660-W