

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION E. 1/4 SW

SEC. 1 TWP. 34 RGE. 30W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schell

Operator Hannock Oil - Gas Co Address Box 631 Comanche Texas

Field _____ County Woods

Total Depth 5983 Feet.

Plugging Contractor Service Well Co

Plugging Contractor's License No. DR

Address 515 Kennedy Bldg Tulsa Okla.
(Describe briefly the manner in which the well was plugged)

13 3/4" 720' C.W.C. 9 7/8" 2650' C.W.C. 800 A
hole filled with heavy rotary mud
to 600' set Plug Punch. 35' x cement
through drill pipe. Mud to 35' set Plug
filled to pass of collar with cement
Cement Pumped by Galveston Cementing Co
B. Boyd in charge for co.

M. L. Rivers
District Conservation Agent

Date 9-13-55

PLUGGING
FILE SEC. 2 T. 34 R. 30W
BOOK PAGE 149 LINE 41

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1955
CONSERVATION DIVISION
Wichita, Kansas

LOG OF
THE SHAMROCK OIL AND GAS CORPORATION
JOHN I. SCHELL NO. 1
(Section 2, Township 34 South, Range
30 West, Meade County, Kansas)

0'	-	475'	Caliche and coarse sand
475'	-	575'	Gravel
575'	-	740'	Red Beds
740'	-	1,340'	Red Beds and Gyp
1,340'	-	2,581'	Shale, salt, and anhydrite
2,581'	-	2,707'	Anhydrite
2,707'	-	3,079'	Dolomite
3,079'	-	3,275'	Lime and Shale
3,275'	-	3,582'	Chalky lime
3,582'	-	5,808'	Lime and shale
5,808'	-	5,922'	Shale and sandy lime
5,922'	-	5,983'	Lime and shale

TOPS

Lansing - 4,632'
Marmaton - 5,283'
Cherokee - 5,470'
Morrow - 5,808'
Mississippian - 5,922'

Elevation: 2,699' Kelly Bushing

PLUGGING

SEC 2 T34 R30W

PAGE 149 LINE 41