

15-119-20243-00-00

KANSAS

Form CP-3
Rev. 6-4-68

RECEIVED
MAY 19 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

Authority April 23, 1980
API Number 15 - - (of this well)

Operator's Full Name Kennedy & Mitchell Inc.
Complete Address PO Box 1578 Liberal Kansas 67901
Lease Name Davis Ranch Well No. 8-94
Location E. NE. SW Sec 13 Twp. 34 Rge. 28 (E) (W) -
County Meade Total Depth 6199'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Sargents Casing Pulling
Address Liberal Kansas License No. 511
Operation Completed: Hour 3:00 PM Day 14 Month May Year 1980

The above well was plugged as follows:

There was 1511' of 8 1/8" surface casing
4 1/2" set to 6199' plugback at 5950' perforations
at 5915-5816. 2nd set perforations at 4375-
4352. 1st Plug at 5915 with 15 lbs cement &
2 shells. 2nd Plug at 4375 with 10 lbs cement
1 shell. 3rd plug at 1500' with 35 lbs cement
4th plug at 750 with 25 lbs cement. 3rd plug
at 40-0 with 10 lbs cement. There was 2343'

I hereby certify that the above well was plugged as herein stated.

of 4 1/2" salvaged.

Signed Clarence Thomas
Well Plugging Supervisor

DATE 5-19-80
INV. NO. 2175-w