

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION Center NW of NW

SEC. 25 TWP. 34 RGE. 30

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. D2 Lease Adams A. W.

Operator Columbian Fuel Corporation Address Box 994, Liberal, Kansas

Field \_\_\_\_\_ County Meade

Total Depth 2740 Feet.

(Describe briefly the manner in which the well was plugged)

9 5/8 casing collapsed at 1320' Parted at 1000' Moved location 60' south.

Casing was cemented with 500 sacks of cement and 75 sacks of Strata Crete by Hall-

-iburton. 2740' to 320' heavy mud.

320' to 208' Cement plug.

208' to 40' Heavy Mud.

40' to 0 Cement plug.

Steel plate welded on top of casing.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 19 1952

CONSERVATION DIVISION  
Wichita, Kansas

R. J. Phillippe  
District Conservation Agent

Date February 10, 1952.