

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
DEC 18 1973
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217Operator's Full Name Underwood Oil Company Inc.Complete Address 420 Oil & Gas Building, Wichita, Falls, Texas 76301Lease Name Adams Well No. XX H-1Location C NE NW Sec. 23 Twp. 34 Rge. 30 XE (W)County Meade Total Depth 6532'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Sargents Casing PullingAddress Box 506, Liberal, Kansas License No. 511Operation Completed: Hour 4:00Pm Day 12 Month 12 Year 1973

The above well was plugged as follows:

16" to 92' Circulated w/ cement. 8 5/8" to 1533' circulated w/ cement.4 1/2" to 6150' cemented. Top perforations 5857'Plug bottom w/ 20 sacks cement. Top of cement 5600'Mud 5600' to 900' Spotted 35 sacks cement 900' to 800'Mud 800' to 45' Plug, Halls & 15 sacks cement 45' to 0'.Company Pump Pulled 3230' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging SupervisorDATE 12/18/73
INV. NO. 8308-W