


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Weade County, Sec. 4 Twp. 34S Rge. 30 W (W)  
Location as "NE/CNW/SW" or footage from lines C SE/4  
Lease Owner Panhandle Development Co., Inc.  
Lease Name Payne Well No. 1  
Office Address 19 E. 11th Street, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-27 1960  
Application for plugging filed 19    
Application for plugging approved 19    
Plugging commenced 7-12 1960  
Plugging completed 7-13 1960  
Reason for abandonment of well or producing formation Formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19    
Was permission obtained from the Conservation Division or its agents before plugging was commenced?   

Name of Conservation Agent who supervised plugging of this well Broadfoot  
Producing formation None Depth to top    Bottom    Total Depth of Well 6000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1421	Left
				4 1/2"-9.5#	5910	2658'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet for each plug set.

Filled hole with pea gravel from 5898' to 5800', Set Baker BIP @ 5780' dumped 20 sacks cement with dump bailed. Dia-Log. Shot 4 1/2" csg off at 2676'. Filled hole with mud to 1600'. Dumped 20 sacks cement with dump bailer - filled hole to 600' - dumped 20 sacks cement with dum bailer - filled hole with mud to 40' - dumped 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Burris Drilling Company  
Address   

STATE OF Kansas, COUNTY OF Seward, ss.  
H. J. Whitman (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. J. Whitman  
(Address)   

SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of August, 1960  
Mary Ann Ooley Notary Public.

My commission expires Sept 4, 1962



TOMMY WARD DRILLING COMPANY  
609 Liberty Bank Building  
Oklahoma City, Oklahoma

July 18, 1960

Panhandle Development Company  
Payne #1  
C SE/4, Section 4-34-30  
Meade, County, Kansas  
Completed June 28, 1960 - TD 6000'

Drilling commenced June 6, 1960, set 36 joints  
8 5/8" surface casing set at 1420' with 600  
sacks pozmix, 200 sacks common cement, 2% c.c.

redbed and shells	0	-	1060
sand, shells and redbed	1060	-	1421
shale and shells	1421	-	2140
shale, redbed, anhydrite	2140	-	2326
anhydrite	2326	-	2852
anhydrite and lime	2852	-	2973
lime	2973	-	3117
lime and chert	3117	-	3164
lime and sand	3164	-	3232
lime	3232	-	4044
lime and shale	4044	-	4560
lime	4560	-	5185
lime and shale	5185	-	5264
lime	5264	-	5388
lime and shale	5388	-	5446
lime	5446	-	5549
lime and shale	5549	-	5580
lime	5580	-	5736
lime and shale	5736	-	5771
lime	5771	-	5845
sand	5845	-	5885
lime	5885	-	6000 TD

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Ran 188 jts 4 1/2" OD 8rd J-55 9.5# Lone Star  
Casing set at 5910' K.B. measurement with  
150 sacks pozmix, plug down at 1:45 a.m.  
June 28, 1960.

We hereby certify that this is a complete drillers log  
of the above described well as taken from our daily  
drilling reports.

TOMMY WARD DRILLING COMPANY

By Mary Limber  
Mary Limber, Secretary