

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20874-00-00

LEASE NAME Meierdienka

WELL NUMBER 2-15

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 15 TWP. 34S RGE. 28 (E) or (W)

COUNTY Meade

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-23-99

Plugging Completed 3-25-99

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coms. Div.  
office within 30 days.

LEASE OPERATOR Eagle Creek Corporation

ADDRESS 107 N. Market, Suite 509 Wichita, Kansas 67202

PHONE#( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by LACY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation KANSAS CITY Depth to Top 4733 Bottom 4777 T.O. 5241

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1235	0
				5 1/2	1962	2450

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Pumped 25 sacks of cement from 4733' to 4500'  
Pumped 50 sacks of cement from 1250' to 1050'  
Pumped 40 sbs of cement from 600' to 400'. Cut off & cap weld on steel 10 plate.  
put 10 sbs of cement from 40-0'

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S Lincoln Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EAGLE CREEK


STATE OF KANSAS COUNTY OF SEDBWICK, ss.

DAVID L. CALLEWAERT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 107 N. MARKET #509 WICHITA

APR 15 1999



BEFORE AND SWORN TO before me this 14<sup>th</sup> day of APRIL, 19 99

Heidi Kortz  
Notary Public

My Commission Expires: 6-12-99