

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

FEB 7 1983
Form CP-4
Rev. 12-15-80
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

15-119-20465-00-00

Give All Information Completely
Make Required Affidavit

COUNTY Meade SEC. 15 TWP. 34S RGE. 28 E/W
Location as in quarters or footage from lines:
C NW SW 1980' FSL & 660' FWL

Lease Owner Mesa Petroleum Co.
Lease Name Meierdierks Well No. #1-15
Office Address Box 2009, Amarillo, TX 79189
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 4-8-81
Application for plugging filed 9-29-82
Plugging commenced 12-31-82
Plugging completed 1-12-83
Reason for abandonment of well or producing formation Non-economical

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
Producing formation NA Depth to top 2980' bottom 3016' T.D. 5975'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.
Council Grove	Dry	2966	2995	4 1/2"	3163'	1600.03'
				8 5/8"	1496'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 2900 feet to 3 feet for each plug set.

1-10, Pumped 25 sks. cem. to 2900'. Shot pipe @ 2494', @ 2027', @ 1605'. 1-11, Pumped 40 sks. cem. from 1605'-1467'. Pumped 25 sks. cem. from 780'-694'. 1-12, Capped w/ 10 sks. cem. from 33'-3'. Welded on steel plate w/name & date using 9.5 lbs. 38 visc. mud between plugs.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mike Proctor's Casing Pullers, Inc.
3022 NW Expwy, #305, Okla. City, OK 73112

STATE OF Texas COUNTY OF Potter, SS.
R. E. Mathis (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. E. Mathis
P.O. Box 2009/Amarillo, TX 79189
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 83

My Commission expires: 4/13/85
Jan Rogers
Notary Public.