

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 119-20814-00-00

LEASE NAME BELLNEY FARMS

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR PANTERA ENERGY COMPANY

SEC. 19 TWP. 34S RGE. 28 (E) or (W)

ADDRESS 724 S. POLK, SUITE 300, AMARILLO, TX 79101

COUNTY MEADE

PHONE#(806) 376-6625 OPERATORS LICENSE NO. 03653

Date Well Completed 8-13-90

Character of Well D&A

Plugging Commenced 8-13-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-13-90

The plugging proposal was approved on 8/13/90 (date)

by CASE MORRIS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom T.D. 3500

Show depth and thickness of all water, oil and gas formations.

AUG 29 1990

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put In	Pulled out
CHASE (2636)	WATER					
COUNCIL GROVE (3118)	WATER	SURF	905	8 5/8	905	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
MUD WEIGHT 9.2#/GAL. CMT PLUGS DISPLACED W/DRILL PIPE. 60 SX CMT @ 2630'.  
60 SX CMT @ 1330'. 50 SX CMT @ 930'. 10 SX CMT @ 60'. 15 SX CMT IN RATHOLE.  
10 SX CMT IN MOUSEHOLE. TOTAL CMT 205 SX 60/40 POZ W/ 6% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TRIAD DRILLING CO. License No. 07345

Address 5400 N. GRAND BLVD., SUITE 310, OKLAHOMA CITY, OK 73112

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PANTERA ENERGY COMPANY

STATE OF TEXAS COUNTY OF POTTER, ss.

SCOTT D. HERRICK (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott D. Herrick

(Address) 724 S. POLK, SUITE 300 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 27TH day of AUGUST, 19 90

Vernice A. Wilson

My Commission Expires: 4/16/91

