

15-119-10229-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Meade County. Sec. 25 Twp. 34 Rge. (E) 30 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center of NW $\frac{1}{4}$ of NW $\frac{1}{4}$

Lease Owner Columbian Fuel Corporation

Lease Name A. W. Adams Well No. D-2

Office Address Box 994, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 8, 19 52

Application for plugging filed February 8, 19 52

Application for plugging approved February 8, 19 52

Plugging commenced February 9, 19 52

Plugging completed February 10, 19 52

Reason for abandonment of well or producing formation Casing Failure on Intermediate String.

If a producing well is abandoned, date of last production --- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. H. Phillippe

Producing formation None Depth to top Bottom Total Depth of Well 2740' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand & Shells	Water	0'	625'	13 3/8"	640'	None
		625'	2740'	9 5/8"	2689'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from Surface feet to feet for each plug set.

- 2740' - Cemented w/500 Sks. Cement, 75 Sks. Strata Crete, Halliburton - 9 5/8" Casing
- 2740' - 320' Heavy Mud
- 320' - 208' Cement & Plug with Halliburton Plug, Below, Halliburton.
- 208' - 40' Heavy Mud.
- 40' - 0' Cement
- 0' - Plate welded over top of casing.

9 5/8" casing collapsed 1320' - Parted 1000' - Moved location 60' South.

RECEIVED
FEB 18 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Columbian Fuel Corporation
Address Box 994, Liberal, Kansas

STATE OF Kansas COUNTY OF Seward, ss.
Robert Grady (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Grady

(Address)

SUBSCRIBED AND SWORN to before me this 15 th day of February, 19 52

Robert B. Gilliam
Notary Public.

My commission expires October 26, 1955

PLUGGING
FILE SEC-25 T-34 R-300
BOOK PAGE 143 LINE 36

LOG OF WELL

CODE GW 2012 Columbian Fuel Corporation SHEET 1
(COMPANY)

STATE Kansas DISTRICT #72 COUNTY Meade

LEASE A. W. Adams WELL NO. 2-D SEC. 25 TWP. 34S R. 30 W.

DATE OF LOG 4/11/52 LOCATION IN SEC. Center of the NW 1/4 fo Section 25 Twp. 34 South
Range 30 West, Meade County, Kansas

LOCATION MADE 1/17/52 COMM. RIGGING UP 1/25/52 COMM. DRILLING 1/25/52 COMP. DRILLING 2/6/52

TOTAL DEPTH 2689' ELEVATION 2636.7' STATE PERMIT NO. _____

DAY DRILLER Bill Jones NIGHT DRILLER Audie Holland CONTRACTOR Helmerich & Payne

CABLE TOOLS FROM 0 TO 0 ROTARY TOOLS FROM 0 TO 2689'

OPEN FLOW CAPACITY _____ M. CU. FT. ROCK PRESSURE _____ GASOLINE CONTENT _____
PER M. CU. FT.

DEPTH IN SAND _____ PRODUCING SANDS AND THICKNESS OF EACH _____

PRODUCTION FIRST 24 HOURS _____ SETTLED PRODUCTION _____ STARTED PRODUCTION _____

DATE TUBED _____ SYPHON SET _____ SIZE _____ FEET _____

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LEFT IN WELL		SHOES		PACKERS		
		FEET	IN.	FEET	IN.	FEET	IN.	LENGTH	MAKE	KIND	LENGTH	SET AT
13 3/8"	36#	651'		-----	-----	651'				Slip Jt. Collar	welded on for	
9 5/8"	36# 25.4#	2689'		-----	-----	2690'				shoe.		

LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. _____ FT. AND INS. _____
BLANK PERFORATED

HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____

REMARKS _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	IN.	FEET	IN.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

KIND OF SHOT _____ SIZE OF SHOT QUARTS _____ NUMBER OF SHOTS _____

NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____

LENGTH OF SHELLS _____ FT. _____ INS. SHOT FURNISHED BY _____ TOP OF SHOT _____

BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____

PRODUCTION BEFORE SHOT _____ PRODUCTION AFTER SHOT _____

NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____
(COMPANY EMPLOYEE)

COMMENCED DRILLING DEEPER _____ COMPLETED DRILLING DEEPER _____

TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ SETTLED PRODUCTION _____

REMARKS: Intermediate Casing 9 5/8" failed therefore making further drilling impossible
Rig was skidded and drilling was commenced on the A. W. Adams D-3.

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

A.W. Adams No. 2-D Well
 NW/4 of NW/4 Section 25 T-34 R-30
 Meade County Kansas
 Columbian Fuel Corp

Casing Record

Set 13 3/8" OD Casing @ 651' With 500 Sacks
 Set 9 5/8" OD Casing @ 2690' With 500 Sacks

Commenced: 1-25-52
 Completed: 2-10-52

0	164	Surface Clay & Sand
164	625	Surface Sand & Shells
625	684	Red Bed
684	880	Red Bed Sand
880	1369	Shells Lime & Shale
1369	1528	Shale Lime & Shells
1528	1550	Shale & Lime Shells
1550	1720	Shale & Lime Shells
1720	1743	Shells Lime & Shale
1743	1773	Shells Lime & Shale
1773	1880	Shale Lime & Anhydrite
1880	1973	Shale Lime & Anhydrite
1973	2044	Shale Lime & Anhydrite
2044	2077	Shale Lime & Anhydrite
2077	2104	Shale Lime & Anhydrite
2104	2116	Shale Lime & Anhydrite
2116	2126	Anhydrite Lime & Shale
2126	2137	Anhydrite Lime & Shale
2137	2172	Anhydrite Lime & Shale
2172	2199	Anhydrite & Lime
2199	2258	Anhydrite & Lime
2258	2264	Anhydrite & Lime
2264	2320	Anhydrite & Lime
2320	2356	Anhydrite
2356	2401	Anhydrite
2401	2468	Anhydrite & Lime
2468	2472	Anhydrite
2472	2520	Anhydrite
2520	2556	Anhydrite
2556	2593	Anhydrite
2593	2600	Anhydrite
2600	2620	Anhydrite
2620	2678	Anhydrite
2678	2707	Anhydrite Cherty Lime
2707	2740	Anhydrite Shale & Lime

Total Depth 2740'

State Of Kansas)

County Of Seward)

I hereby affirm that the above and foregoing is a true and correct copy of the log of our A.W. Adams #D-2 Well, located in the NW/4 of NW/4 Northwest Quarter of Northwest Quarter in Section 25, Township 34 Range 30, Meade County Kansas.

COLUMBIAN FUEL CORPORATION

Robert Grody
 Superintendent

Subscribed and sworn to before me a Notary Public, this 25th day of April, 1952.

Wallace B. Pedigo
 Notary Public

My commission expires June 4, 1955

PLUGGING
 FILE SEC 25 T 34 R 30
 BOOK PAGE 143 LINE 36