

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat.

Meade County, Sec. 23 Twp. 34S Rge. 30 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C-N-E-N-W.
Lease Owner Underwood Oil Co., Inc.
Lease Name Jessie S. Adams Well No. H-1
Office Address 420 Oil & Gas Bldg., Wichita Falls, Texas 76301
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19
Application for plugging filed 11-23 1973
Application for plugging approved 11-25 1973
Plugging commenced 12-8 1973
Plugging completed 12-12 1973
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eyes
Producing formation Depth to top Bottom Total Depth of Well 6532 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Please see attached				8 5/8 4 1/2	1533 6150	none 3230

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

20 sks. of cement @ 5600
35 sks. of cement @ 900 to 800
15 sks. of cement @ 45 to 0

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Seward, ss.
Robert Sargent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Sargent

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 1973
Edith L. Stubblefield
Edith L. Stubblefield Notary Public.

My commission expires October 5, 1975



DUP

WELL RECORD

Underwood Oil Company, Inc.
 Jessie S. Adams et al Well No. H-1
 Sec. 23, T-34S, R-30W, Meade County, Kansas

Ground Elevation: 2662' KB: 2672'

Drilling Contractor: Leben Drilling, Inc.
 5700 Portland
 Oklahoma City, Oklahoma 73112

Well Commenced: 7-17-72 8 5/8" @ 1533' - 150 sacks
 Well Completed: 8-8-72

FORMATION LOG

Toronto	4498' (-1862)
Lansing	4636' (-1964)
Hodges	5142' (-2470)
Marmaton	5316' (-2644)
Morrow	5850' (-3178)
Sand	5888-5910' (-3216)
Siltstone	5928' (-3256)
Chester	5964' (-3292)
Ste. Genevieve	6312' (-3640)
St. Louis	6300' (-3728)
St. Louis Porosity	6466' (-3794)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 31 1974
 CONSERVATION DIVISION
 Wichita, Kansas

UNDERWOOD OIL COMPANY, INC.

R. CLAY UNDERWOOD,
 President

Company Underwood Oil Co., Inc.

Sec. 23 T. 34S R. 30W

Contractor Leben Drilling, Inc.

Loc. C - N.E. - N.W.

Farm AdamsH-1

County Meade Co. KS


Total Depth 6532'

Casing 8 5/8" @ 1533'

Commenced July 17, 1972

Production 4 1/2" @ 6150'

Completed August 10, 1972



Figures Indicate Bottom of Formations

0	-	340	Sand-Clay
340	-	1410	Red Bed-Shale-Anhy.
1410	-	1533	Shale Anhy.
1533	-	1665	Anhy. Shale
1665	-	2226	Shale & Lime
2226	-	2510	Shale Anhy.
2510	-	3836	Lime & Shale
3836	-	3929	Shale & Lime
3929	-	4145	Lime & Shale
4145	-	4537	Shale & Lime
4537	-	4570	Lime & Shale
4570	-	6184	Lime & Shale
6184	-	6232	Lime
6232	-	6322	Lime & Shale
6322	-	6370	Lime
6370	-	6458	Lime & Shale
6458	-	6465	Lime
6465	-	6522	Lime & Shale
6522	-	6532	Lime

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1972
CONSERVATION DIVISION
Wichita, Kansas

State of Oklahoma

SS

County of Oklahoma

I, Leslie Kite of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Adams H-1 Well.

Leslie Kite

Subscribed and sworn to before me this 21st day of August, 1972

My Commission Expires: 5/23/76

Brenda Kay Swink