

15-119-10231-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Meade County, Sec. 23 Twp. 34 Rge. 30 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 660' Fm East & 660' Fm South Line

Lease Owner Columbian Fuel Corp

Lease Name A.W. Adams Well No. D-4

Office Address Box 994... Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-1-52 19

Application for plugging filed 6-6-52 19

Application for plugging approved 6-10-52 19

Plugging commenced 7-1-52 19

Plugging completed 7-10-52 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.J. Phillippe

Producing formation None Depth to top Bottom Total Depth of Well 6112' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand & Shells	Water	0	580'	13 3/8"	643'	0
				8 5/8"	2762'	1021'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

6112' - 4330' Mud
~~2730' - 2600' 50 Sx Cement~~
 2600 - 300' Mud
 4330' - 4200' 50 Sx Cement
 4200' - 2730' Mud
 300' - 290' Rock Bridge
 2730' - 2600' 50 Sx Cement
 290' - 260' 30 Sx Cement
 260' - 25' Mud
 25' - 10' 15 Sx Cement
 Cellar Filled & Casing Covered With 3' Dirt

1021' 8 5/8" OD Casing Recovered

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1952

7-22-52
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Barnes & Sons, Russell, Kansas
Address

STATE OF Kansas, COUNTY OF Seward, ss.

Robert Grady, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Grady

Box 994, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 52

Wallace B. Pedigo
Notary Public.

My commission expires June 4, 1955

23-8390-s 6-51-20M

PLUGGING
FILE SEC 237.3.48-502
PAGE 22 OF 35

A. W. Adams "D" Well No. 4
SE SE Section 23-34S-30W
Meade County, Kansas
Columbian Fuel Corporation

CASING RECORD

Set 13-3/8" Casing @ 643 with 500 sacks
 Set 8-5/8" Casing @ 2762 with 700 sacks

Commenced: April 17, 1952
 Completed: May 31, 1952

Surface Sand, Clay & Shells	0	360
Clay & Sand Shells	360	665
Redbed	665	1047
Redbed, Shells & Shale	1047	1380
Anhydrite & Shale	1380	1400
Anhydrite & Lime Shells	1400	1680
Shale, Shells & Salt	1680	1712
Red & Blue Shale & Shells	1712	1775
Shale, Anhydrite & Shells	1775	2141
Anhydrite, Shale & Salt	2141	2245
Anhydrite, Shale, Shells & Salt	2245	2267
Anhydrite, Shale & Salt	2267	2614
Anhydrite, Shale, Salt & Lime	2614	2646
Anhydrite, Lime & Shale	2646	2760
Cherty Lime & Shale	2760	2812
Lime & Shale	2812	3283
Lime	3283	3357
Lime & Shale	3357	4015
Shale & Shells	4015	4165
Shale & Lime	4165	4243
Shale & Lime Shells	4243	4311
Shale & Lime	4311	4333
Shale & Lime Shells	4333	4490
Lime & Shale	4490	4798
Lime, Shale, some Junk	4798	4801
Lime, Shale & Junk	4801	4804
Lime & Shale	4804	4840
Sandy Lime & Shale	4840	4868
Lime & Shale	4868	4984
Lime & Chert	4984	5012
Cherty Lime & some Shale	5012	5042
Cherty Lime & Shale	5042	5125
Cherty Lime	5125	5178
Cherty Lime & Shale	5178	5310
Lime & Shale	5310	5480
Lime & Shale, Cherty	5480	5520
Lime & Shale	5520	5774
Shale & Sandy Lime	5774	5782
Lime & Shale	5782	5952
Sandy Lime	5952	5978
Lime & Shale	5978	6112
TOTAL DEPTH		6112

STATE OF OKLAHOMA)
)^{ss}
 CITY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of your A. W. Adams "D" Well No. 4, located in the Southeast Quarter of the Southeast Quarter of Section 23, Township: 34 South, Range 30 West, Meade County, Kansas.

HELMERICH & PAYNE, INC.

J. H. Giffin

 Vice-President

Subscribed and sworn to before me a Notary Public, this 10th day of June, 1952.

Richard B. Gifford

 Notary Public
 STATE OF OKLAHOMA
 JUL 22 1952
 CONSERVATION DIVISION
 Wichita, Kansas

My commission expires March 13, 1954.

LOG OF WELL

CODE GW 2022 Columbian Fuel Corp SHEET _____
 (COMPANY)
 STATE Kansas DISTRICT 72 COUNTY Meade
 LEASE A.W. Adams WELL NO. D-4 SEC. 23 TWP. 34 R. 30
 DATE OF LOG 7-15-52 LOCATION IN SEC. 660' From East Line & 660' From South Line
 LOCATION MADE 4-12-52 COMM. RIGGING UP 4-16-52 COMM. DRILLING 4-17-52 COMP. DRILLING 6-1-52
 TOTAL DEPTH 6112' ELEVATION 2659.6' Ground STATE PERMIT NO. _____
 DAY DRILLER Abe Hillsberry NIGHT DRILLER Roy Hillsberry CONTRACTOR Helmerich & Payne
 CABLE TOOLS FROM _____ TO _____ ROTARY TOOLS FROM _____ TO _____
 OPEN FLOW CAPACITY _____ M. CU. FT. ROCK PRESSURE _____ GASOLINE CONTENT _____ PER M. CU. FT.
 DEPTH IN SAND _____ PRODUCING SANDS AND THICKNESS OF EACH _____
 PRODUCTION FIRST 24 HOURS _____ SETTLED PRODUCTION _____ STARTED PRODUCTION _____
 DATE TUBED _____ SYPHON SET _____ SIZE _____ FEET _____

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LEFT IN WELL		SHOES		PACKERS		
		FEET	IN.	FEET	IN.	FEET	IN.	LENGTH	MAKE	KIND	LENGTH	SET AT
13 3/8"	48 & 54#	642.92'				642.92'						
8 5/8"	28#	2762.07'		1021'		1741.07'						

LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	IN.	FEET	IN.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

KIND OF SHOT _____ SIZE OF SHOT QUARTS _____ NUMBER OF SHOTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FT. _____ INS. SHOT FURNISHED BY _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 PRODUCTION BEFORE SHOT _____ PRODUCTION AFTER SHOT _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ SETTLED PRODUCTION _____

REMARKS: Dry Hole No 5 1/2" O.D. Casing Ran .. Well Plugged By Barnes & Son
Russel, Kansas.
 STATE CORPORATION COMMISSION
 JUL 22 1952
 CONSERVATION DIVISION
 Wichita, Kansas

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.