

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20899

LEASE NAME Adams

WELL NUMBER 1-22

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1650 Ft. from (S)N line of Section (circle one)

990 Ft. from (E)W line of Section (circle one)

LEASE OPERATOR Merex Resources, Inc.

SPOT LOCATION CSW - NE - SE -

ADDRESS P.O. Box 50955

SEC. 22 TWP. 345 S. RGE 30W (E) or (W)

CITY, STATE, ZIP Amarillo, TX 79159

COUNTY Meade

PHONE#(806) 374-2369 OPERATORS LICENSE NO. 31581

Date Well Completed 2-17-95

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 7-6-95

Date Plugging Completed 7-7-95

The plugging proposal was approved on July 6, 1995 (date)  
by Glen Barlow (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Council Grove Depth to Top 3187 Bottom 3263 T.P. 3715 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Anhydrite	none			8 5/8	1514	none
Marmaton	Oil	5300	5350	4 1/2	5435	2544
Council Grove	Gas	3010	3530	4 1/2	5435	2544

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Set CIBP @ 3130 with 2 sx cement. Pump 40 BBL mud down casing load hole.  
Shot 4 1/2 casing off @ 2544' and laydown. Pump 50 sx from 1545' to 1371',  
pump 40 sx plug from 600' to 468' and pump 10 sx plug from 30' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor H & K Plugging and Salvage

License No. 31705

Address P.O. Box 2742, Highway 152 West, Pampa, TX 79066

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Merex Resources, Inc.


STATE OF Texas COUNTY OF Potter, ss.

Ed Podzemny (Employee of Operator or (Operator) of above-described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ed Podzemny

(Address) P.O. Box 50955, Amarillo, TX 79159

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1995



Lynda B. Banger  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 17 1995

CONSERVATION DIVISION  
WICHITA, KS