


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Location as "NE/CNW/SE/SW" or footage from lines Meade County, Sec. 20 Twp. 34S Rge. (E) 30W
Lease Owner Murfin Drilling Company
Lease Name Holmes Well No. 1 (OWWO)
Office Address 617 Union Center, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5, 19 73
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 5, 19 73
Plugging completed October 5, 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1319'	8-5/8"	1319'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 1000 Feet,
35 sax Cement Plug; Mud to 40 Feet, 1/2 sax
Hulls, Plug Bridged & 15 sax Cement to
Base of Cellar. Job Completed @ 10 P.M.


RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton
Address P. O. Box 129, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employer or owner or operator) of the above described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 10th day of October 19 73.
Louise K. Whitted
November 26, 1974. Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1973
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

HOLMES NO. 1 (OWWO)

OPERATOR:	Murfin Drilling Co.	DESCRIPTION:
CONTRACTOR:	Sage Drilling Co.	C SW SW
COMMENCED:	September 22, 1973	Sec. 20-34S-30W
		Meade County, Kansas
COMPLETED:	October 5, 1973	TOTAL DEPTH: 6320'

<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
0	4550	Washed hole down to old TD of 4550 Feet. Ran DST#1 4470 Feet to 4490 Feet.
4550	4845	Drilled new hole. Drilling in Lime.
4845	4920	Drilling in Lime & Shale.
4920	5645	Drilling in Lime. Ran DST#2 5513 Feet to 5555 Feet.
5645	5725	Drilling in Lime & Shale.
5725	6320	Drilling in Lime. Ran DST#3 5695 Feet to 5765 Feet. Ran DST#4 5695 Feet to 5844 Feet. Ran Log. D&A. Hole Plugged.

I certify that this is a true and correct copy of the washdown operations and drilling deeper on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 10th day of October, 1973.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.