

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
DEC 2 1933
12-2-66
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Gruenerwald & Assoc. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Wm. Gruenerwald & Assoc.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name: R.E Adams Well No. 1

Location: SE NE Sec. 4 Twp. 35 Rge. 30 (E)(W)

County Meade Total Depth 3360' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole X

Mr. Walker was instructed to plug the well as follows:

13 3/8" to 590' circulated w/ cement., 8 5/8" to 2550' cemented,

Mud 3360' to 600' Spotted 50sacks cement 600' to 450'

Mud 450' to 45' Plug, Hulls & 15 sacks cement 45' to 00.

Very truly yours,

Edgar J. Eves
Conservation Division Agent