



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Deem of Braden-Deem has this

date requested permission to plug the following described well:

Mr. Deem guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 200 E. 1st, Wichita, Kansas

Lease Name: Banks Well No. 2

Location: NE NW Sec. 3 Twp. 35 Rge. 30 (E) (W)

County: Meade Total Depth 6447' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deem was instructed to plug the well as follows:

8 5/8" to 1855' circulated w/ cement. 5 1/2" to 6146' cemented.


Top perforations 6315' Plug bottom w/ 20 sacks cement.

Top of cement. 6200' Mud 6200' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent