

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


Dear Sir:

Mr. Clark of Red Clark has this

date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.Operator's full Name: Red Clark Inc.Complete Address: Liberal, KansasLease Name: Adams Ranch Well No. 1Location: C SW SE Sec. 2 Twp. 35 Rge. 30 (E) (W)County: Meade Total Depth 6400' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Clark was instructed to plug the well as follows:8 5/8" to 1510' circulated w/ cement. 5 1/2" to 6388' cement,Top perforations 5764' Plug bottom w/ 20 sacks cement.Top of cement 5550' Mud 5550' to 900'Spot 30 sacks cement 900' to 800' Mud 800' to 40'Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent