

15-119-10342-0001

FORM - CP-2  
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 9 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Colo. Oil & Gas Corp. has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil & Gas Corporation

Complete Address: Box 158, Liberal, Kansas

Lease Name: Adams "G" Well No. 1

Location: NW NW SW Sec. 1 Twp. 35 Rge. 30 (E) (W)

County Meade Total Depth 6310' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1159' circulated w/ cement. 5 1/2" to 5860' cemented.

No Perforations Plug bottom w/ 20 sacks cement,

Top of cement 5650' Mud 5650' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 45'

plug, Hulls & 15 sacks cement 45' to 0 Pump

Very truly yours,

Edward J. Lewis  
Conservation Division Agent