

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clark of Red Clark has this

date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Red Clark

Complete Address: Box 564, Liberal, Kansas

Lease Name: Nusser Well No. 1

Location: NE NW Sec. 13 Twp. 35 Rge. 31 (E) (W)

County: Seward Total Depth 4750' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

8 5/8" to 1455' circulated w/ cement. 4 1/2" to 4748' cemented.


Top perforations 4471' Plug bottom w/ 15 sacks cement,

Top of cement. 4350' Mud 4350' to 900'

Spot 30 sacks cement 900' to 800' Mud 800' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent