

State of Kansas

FORM CP-2



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

7 April 1982

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1982  
VERBAL PERMIT FORM  
(to be filed by Plugging Agent)  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Pat Smith of Louvie's Leasing has this date requested permission to plug the following described well:

Operator's Full Name: Kennedy Mitchell Inc.

Complete Address: 215 One Twenty Bldg. Wichita, Kansas 67202

Lease Name: Risley Well No. 45-695

Location: C-NW Sec. 5 Twp. 35 Rge. 31 (E) (4)

County: Seward Total Depth: 6500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Smith was instructed to plug the well as follows:

They have 1526' of 8 5/8" surface casing cement circulated. 1st plug 1581' with 50 sbk of cement. 2nd plug at 527' with 25 sbk of cement. 3rd plug 40' to 0' on solid bridge with 10 sbk of cement. Then they circulated 10 sbk of cement in rat hole & 10 sbk in mouse hole. Halliburton Co. accomplished the plugging by pumping cement through drill pipe. They ran a bonding log on surface casing before plugging.

Very truly yours,

Paul A. Luttie

Conservation Division Agent