

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Stromquist of Parlay Oil has this

date requested permission to plug the following described well:

Mr. Stromquist guarantees payment of the plugging fee.

Operator's full Name: Parlay Oil Inc.

Complete Address: Box 488, Spearman, Texas

Lease Name: Reed Well No. 1

Location: C SE NE Sec. 4 Twp. 35 Rge. 31 (E)(W)

County: Seward Total Depth 6542' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stromquist was instructed to plug the well as follows:

8 5/8" to 1418' circulated w/ cement. Mud 6542' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement. 45' to 0'.

Very truly yours,

Conservation Division Agent