

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lillard of Blaik Oil Col has this

date requested permission to plug the following described well:

Mr. Lillard guarantees payment of the plugging fee.

Operator's full Name: Blaik Oil Company

Complete Address: 203 Park Ave., Oklahoma City, Oklahoma

Lease Name: Schlehofer Well No. 1

Location: SW NE Sec. 3 Twp. 35 Rge. 31 (E) (W)

County: Seward Total Depth 5485' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lillard was instructed to plug the well as follows:

8 5/8" to 1112' Circulated w/ cement. 4 1/2" to 5359' cemented.

Top perforations 5235' Plug bottom w/ 15 sacks cement.

Top of cement 5100' Mud 5100' to 1100'

Spotted 35 sacks cement 1100' to 1000' Mud 1000' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent