

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Casey of J.M. Huber Corp. has this date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 888, Spearman, Texas 79081

Lease Name: Light Estate "C" Well No. 1

Location: C SW SW Sec. 2 Twp. 35 Rge. 32 (S) (W)

County: Seward Total Depth 6327' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Casey was instructed to plug the well as follows:

13 3/8" to 620' ciru. w/ cement. 9 5/8" to 2400' ciru. w/ cement.

5 1/2" to 6315' cemented. Top perforations 5961'

Plug bottom w/ 25 sacks cement Top of cement 5796'

Mud 5796' to 1000' Spot 40 sacks cement 1000' to 900'

Mud 900' to 40' Plug Hulls & 15 sacks cement 40' to 0'.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Edgar J. Evers
 Conservation Division Agent