

15-175-10182-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of J.M. Huber has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: J.M Huber Corporation

Complete Address: Box 911, Amarillo, Texas

Lease Name: Neff Well No. 2

Location: NW NE Sec. 2 Twp. 35 Rge. 32 (E) (W)

County: Seward Total Depth 6145' ~~6100'~~ Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Casey was instructed to plug the well as follows:

13 3/8" to 400' circulated w/ cement. 9 5/8" to 2400' circulated w/ cement.

7" to 6145' cemented. Top perforations 5932'

Plug bottom w/ 60 sacks cement. Top of cement 5848'

Mud 5848' to 900' Spot 40 sacks cement 900' to 800'

Mud 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Conservation Division Agent