

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Woolridge of Amoco has this

date requested permission to plug the following described well:

Mr. Woolridge guarantees payment of the plugging fee.

Operator's full Name: Amoco Production Co.

Complete Address: Box 432, Liberal, Kansas

Lease Name: Matkin Gas Unit "A" Well No. 1

Location: 1700' FNL & 660' FWL Sec. 14 Twp. 35 Rge. 33 XX (E)(W)

County: Seward Total Depth 6250' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole


Mr. Woolridge was instructed to plug the well as follows:

8 5/8" to 1540' circulated w/ cement. Mud 6250' to 1007'

Spot 35 sacks cement 1007' to 907' Mud 907' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent