

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of An-son Corporation has this  
date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: An-son Corporation

Complete Address: 3814 North Sante Fe, Oklahoma City, Oklahoma

Lease Name: Howland Well No. 1

Location: C NE SW Sec. 10 Twp. 35 Rge. 33 (W)

County Seward Total Depth 6800' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Dunkin was instructed to plug the well as follows:

8 5/8" to 1532' Circulated w/ cement. 5 1/2" to 6612' cemented.

Top Perforations 6148' Plug Bottom w/ 25 sacks cement.

Top of cement 6100' MUd 6100' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 40'

Plug, Halls & 15 sacks cement 40' to 0.

Very truly yours,

Edgar J. Evans  
Conservation Division Agent