

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202
RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1962

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

CONSERVATION DIVISION
Wichita Kansas

Dear Sir:

Mr. Ted Brown of Dawson Well (Reg 3) has this date requested permission to plug the following described well:

Operator's Full Name: Ladd & Sukowicz

Complete Address: 1600 Broadway #1730 Denver Colorado 80202

Lease Name: King Well No. # 1-8

Location: C-N 1/2 - SW Sec. 8 Twp. 25 Rge. 23 (E) (W)

County: Seward Total Depth: 6685 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Brown was instructed to plug the well as follows:

8 5/8" - 1515 FT SR. cm w/ 800ST Halliburton Light & Class H w/ 3% CaCl.
Ordered 200ST 50 Forming 4% Gel- 3% Co-cl. & 8 5/8" Plug
Spot with Drill Stem - with heavy mud between all Plug.

1st Plug @ 3000 FT w/ 25ST cnt.

2nd Plug @ 2560 FT w/ 35ST cnt.

3rd Plug @ 1500 FT w/ 60ST cnt.

(By Halliburton)

4th Plug @ 330 FT w/ 50ST cnt.

5th Plug solid Buds @ 40 FT w/ 10ST cnt.

10ST In Pat hole 10ST In mouse hole

circulate w/ front of pipe

M. J. Schmidt
Conservation Division Agent

Very truly yours;