

15-119-00169-0001

Form CP-3
Rev. 6-26-62

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cleary Petroleum Corporation

Complete Address: 310 Kermac Bldg,, Oklahoma City, Oklahoma 73102

Lease Name Adams "K" Well No. 1

Location SE NE Sec. 11 Twp. 35 Rge. 30 (E) (W)

County Meade Total Depth 6300'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Lillard Pipe Pullers

Address: Box 962, Woodard, Oklahoma License No. 618

Operation Completed: Hour 2:00PM Day 18^m Month 11 Year 1968

The Above well was plugged as follows:

8 5/8" to 2543' circulated w/ cement. 5 1/2" to 5826' cemented.

3 1/2" liner 5684' to 6299' Top perforations 6254'

Plug bottom w/ 20 sacks Top of cement 5550'

Mud 5550' to 1700' Spotted 35 sacks cement 1700' to 1600'

Mud 1600' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

C & L Pump Truck, Woodard, Okla.

Pulled 2516' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

11/21/68
8858-W