

rk

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Authority to plug issued
Jan 14, 1976

RECEIVED
CORPORATION DIVISION
JAN 26 1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name R. Clay Underwood
Complete Address Box 1068, Liberal Kans. 67901
Lease Name Jessie S. Adams Well No. A-3
Location E. SE N.W. Sec. 8 Twp. 35 Rge. (E) (W) 30
County Meade Total Depth 3060
Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling
Address Liberal Kans 67901 License No. 511

Operation Completed: Hour 11:30 AM Day 22 Month Jan Year 1976

The above well was plugged as follows:

There was 1442' of 8 1/2" surface casing
4 1/2" set to 3020. Perforations were from
2936-2930. 1st plug at 3020 with 10
sacks cement. 2nd plug at 1400' with
40 sacks cement. 3rd plug at 40-0 with
10 sacks cement. There was 2010'
of 4 1/2" casing salvaged

I hereby certify that the above well was plugged as herein stated.

Signed: Clarence Thomas
Well Plugging Supervisor

1-28-76
2641-W