

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-8-81

DEC - 8 1981

CONSERVATION DIVISION
Wichita Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name B. & B. Brown Industries, Inc.

Complete Address Box 632 Spearman, Texas 79081

Lease Name Eddy Well No. 2

Location C-NE-NE Sec. 6 Twp. 35S Rge. 30E (East)(West)

County Manda Total Depth 6220'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling

Address Box F Sublett Kansas 67877 License No. 766

Operation Completed: Hour: 3:30 PM Day: 5 Month: December Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 1457' of 8 5/8" surface casing cement circulated. They ran 4510' of 4 1/2" production pipe cemented it with 150 sbp of cement. They set a cast iron plug at 4337'. Three perforations were at 4318' to 4334'. 1st plug at 4337' with 2 sbp of shells & 15 sbp of common cement pumped to bottom. 2nd plug at 1450' with 35 sbp of common cement. 3rd plug 40' to 0' on solid bridge with 10 sbp of cement. Plugging accomplished by Midwest Casing Pulling Co. out of Sublett Kansas. They removed 2442' of 4 1/2" production pipe.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Lutter
Conservation Division Agent

1-19-82

89-41-W

5/12/02