

AP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Horizon Oil & Gas Company

Complete Address: Box 7, Spearman, Texas

Lease Name Adams "B" Well No. 1-5

Location C SW NE Sec. 5 Twp. 35 Rge. 30 (E) (W)

County Meade Total Depth 6320'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 6:15PM Day 1 Month 9 Year 1967

The Above well was plugged as follows:

8 5/8" to 1360' circulated w/ cement 4 1/2" to 6310' Cemented

Top perforations 6120' Plug bottom w/ 15 sacks cement

Top of cement 5960' Mud 5960' to 700'

Spotted 40 sacks cement 700' to 600' Mud 600' to 40'

Plug, Halls & 10 sacks cement 40' to 0' Company Pump

Rilled 4932' of 4 1/2" casing

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: *Edward J. Egan*
Well Plugging Supervisor

DATE 9/6/67
FILED 6260-W