

15-119-10347-0000  
R

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name S&S Pipe & Supply Company  
Complete Address: 1209 Mid-Continent Bldg., Tulsa, Oklahoma 74103  
Lease Name Fox Well No. 4  
Location NE SE NE Sec. 3 Twp. 35 Rge. 30 (E) (W)  
County Meade Total Depth 5963'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:00PM Day 22 Month 6 Year 1968

The Above well was plugged as follows:

8 5/8" to 1376' circulated w/ cement. 5 1/2" to 5962' cemented.  
Top perforations 5910' Plug bottom w/ sand & 5 sacks cement .  
Top of cement 5850' Mud 5850' to 700'  
Rock Bridge & 35 sacks cement 700' to 600' Mud 600' to 45'  
Rock Bridge & 15 sacks cement 45' to 0'  
Pulled 2800' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eubank  
Well Plugging Supervisor

FILED  
JUN 25 1968  
NO. 7999-W