



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Red Clark Inc

Complete Address Liberal, Kansas 67901

Lease Name Adams Ranch Well No. 1

Location C SW SE Sec. 2 Twp. 35 Rge. 30 ~~(E)~~ (W)

County Meade Total Depth 6400'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 1:30 Pm Day 27 Month 8 Year 1974

The above well was plugged as follows:

8 5/8" to 1510' circulated w/ cement.	5 1/2" to 6388' cemented.
Top perforations 5764'	Plug bottom w/ 20 sacks cement.
Top of cement 5550'	Mud 5550' to 900'
Spotted 30 sacks cement 900' to 800'	Mud 800' to 40'
Plug, Hulls & 10 sacks cement 40' to 0'.	Company Pump
Pulled 4407' of 5 1/2" casing.	

I hereby certify that the above well was plugged as herein stated.

9/4/74
9823-W

Signed: [Signature]
Well Plugging Supervisor