

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name J.M.Huber Corp.

Complete Address: Box 978 Liberal, Kansas

Lease Name Loflin-Hawks. Well No. 1

Location C NE SW Sec. 18 Twp. 35 Rge. 31 (E) (W)

County Seward Total Depth 8006'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Daco Lease & Well Servicing Company

Address: Borger, Texas License No. 138

Operation Completed: Hour 5 PM Day 19 Month 10 Year 63

The Above well was plugged as follows:

13 3/8"-556' Circulated w/cement. 9 5/8"-2370' Cemented. 7"-6354' Cemented.

Plug back to 6037' Perforations 6014' to 5995'

Plug bottom w/20 Sax.cement 6037' to 5937' Mud 5937' to 550'

50 Sax.cement 550' to 488' Mud 488' to 50'

Rock bridge 50' to 40' 30 Sax.cement 40' to surface.

Pulled 4020' 7" pipe. Pulled 612' 9 5/8" pipe. Company Pump.

Weld cap on surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10/23/63  
INV. NO. 7939-W

Signed: [Signature]  
Well Plugging Supervisor