

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORTAPI Number 15-175-20,599-0000200 Colorado Derby Building
Wichita, KS 67202Operator's Full Name Kimbarb Oil & Gas Co.Complete Address 1580 Lincoln, Suite 700, Denver Colo. 80203Lease Name Alice Well No. 2Location SW-NW Sec. 17 Twp. 35SR Rge 3/W (East) (West)County Seward Total Depth 5650'Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Da Mack Drilling Inc.Address Box 1164 Great Bend Kans. 67530 License No. _____Operation Completed: Hour: 1:45 AM Day: 1 Month: March Year: 19 82Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They have all fresh water behind surface casing.
1st plug push rubber plug to 1500' & pumped 40 bbl of
cement on top of it. 2nd plug 600' with 35 bbl of cement.
3rd plug 40' to 0' with 15 bbl of cement on solid bridge.
Then circulated 10 bbl of cement in mat hole & 5 bbl of
cement in mouse hole. The cement was pumped through
drill pipe with hole full of heavy mud. The plugging
was accomplished by Halliburton Co.

Amount of Surface Casing: 1520' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This well is out of my area, but I have
been on wells being plugged by Mr. Divine & he will
do it right.

Signed: Paul Luthi
Conservation Division Agent

3-10-82

9693-W