



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Red Clark

Complete Address Box 564, Liberal, Kansas 67901

Lease Name Nusser Well No. 1

Location NE NW Sec. 13 Twp. 35 Rge. 31 (E) (W)

County Seward Total Depth 4750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00Pm Day 29 Month 8 Year 1974

The above well was plugged as follows:

- 8 5/8" to 1455' circulated w/ cement. 4 1/2" to 4748' cemented.
- Top perforations 4471' Plug bottom w/ 15 sacks cement.
- Top of cement 4350' Mud 4350' to 900'
- Spotted 30 sacks cement 900' to 800' Mud 800' to 40'
- Plug, Hulls & 10 sacks cement 40' to 0' Company Pump
- Pulled 2551' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

9/4/74
9831-W

Signed: [Signature]
Well Plugging Supervisor