

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20, 383-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name B. & B. Farm Industries

Complete Address Box 638, Spearman, Texas 79081

Lease Name Raymond Well No. 1

Location 200' W of C-SW-SE Sec. 12 Twp. 35 Rge. 31 (East)(West)

County Seward Total Depth 6170'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling

Address Box F, Sublette, Kans 67877 License No. 766

Operation Completed: Hour: 3:00PM Day: 6 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They had run 6161' of 4 1/2" production pipe with a plugback at 6142'. They perforated the 4 1/2" from 6000' to 6082'. 1st plug pumped through 4 1/2" with 1 1/2 lbs huller 20 lbs of cement. 2nd plug at 1600' with 35 lbs of cement. 3rd plug at 750' with 25 lbs of cement. 4th plug 40' to 0' on solid bridge with 10 lbs of cement. They recovered 2402' of 4 1/2" production pipe. The plugging was accomplished by Midwest Casing Pulling.

Amount of Surface Casing: 8 3/8" at 1542'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on another job at this plugging.

Signed: Paul A. Luttie
Conservation Division Agent

Rec. 9-2-82
9-9-82
1065-W