

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Blaik Oil Company

Complete Address 203 Park Ave., Oklahoma City, Oklahoma

Lease Name Schlehofer Well No. 1

Location SW NE Sec. 3 Twp. 35 Rge. 31 (E) (W)

County Seward Total Depth 5485'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Lillard Casing Pulling

Address Woodard, Oklahoma License No. 618

Operation Completed: Hour 11:00PM Day 13 Month 10 Year 1970

The above well was plugged as follows:

8 5/8" to 1412' circulated w/ cement. 4 1/2" to 5359' cemented.

Top perforations 5235' Plug bottom w/ 15 sacks cement

Top of cement 5100' Mud 5100' to 1100'

Spotted 35 sacks cement 1100' to 1000' Mud 1000' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. B J Pump Truck.

Pulled 3006' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Eves*
Well Plugging Supervisor

10-19-70
2703-10