

RECEIVED  
STATE CORPORATION COMMISSION

9-12-79  
SEP 12 1979 CP-3

Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

Authority June 13, 1978  
API Number 15 - - (of this well)

Operator's Full Name J. M. Huber Corporation  
Complete Address 2450 Liberty Tower, Oklahoma City, Okla.  
Lease Name Freese Well No. 1  
Location C. NE. NW. Sec. 19 Twp. 35 Rge. (E) (W12)  
County Seward Total Depth 6126  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Sargents Casing Pulling  
Address Liberal Kansas License No. 511  
Operation Completed: Hour 5:00 PM Day 7 Month Sept Year 1978

The above well was plugged as follows:

There was 677' of 13 3/8" surface casing 2392'  
of 9 5/8" surface casing. 7" set to 6126. 4 1/2"  
set to 5921. perforation was from 5946-  
5967. 1st plug at 5967-5800 with 20  
lbs cement 1 1/2" shells. 2nd plug at 2300'  
with 35 lbs cement. 3rd plug at 600'  
with 25 lbs cement. 4th at 4800 with 15 lbs  
cement. There was 4800' of 4 1/2" salvaged.

I hereby certify that the above well was plugged as herein stated.

and 2710' of 7" salvaged. Signed: Clarence Thomas  
Well Plugging Supervisor

9-13-78

8055-W